BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Yelahanka Division
B.B.M.P. Bangalore - 64

APPROVED SCHEDULE - B

Name of work: Providing and fixing cobble stone pathway at yelahanka new town 5th phase in ward No- 02 of yelahanka Sub Division.

Sl. No.	Description	Unit	Approved Quantity	Approved Rate Technical Manager, (west) KRIDL BBMP.	
				In Figures	In Words
1	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No	Cum	479.94	166.42	Rupees one hundred sixty six and paise forty two only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M	Cum	479.94	100.00	Rupees one hundred and paise zero only
3	KSRRB M300-53: construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification	Cum	383.58	320.12	Rupes three hundred twenty and paise twelve only
4	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS	Cum	155.78	5159.02	Rupees five thousand one hundred fifty nine and paise two only
5	KSRB 14.6-2 : Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufactures of blocks of approved size , shape and colour with a minimum compressive strength of 281kgs per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour, curing complete as per specifications.	Sqm	1279.91	966.72	Rupees nine hundred sixty six and paise seventy two only

Sl. No.	Description	Unit	Approved Quantity	Approved Rate Technical Manager, (west) KRIDL BBMP.	
				In Figures	In Words
6	KSRB 15.19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughtly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	8.00	27.56	Rupees twenty seven and paise fifty six only
7	KSRRB 800-1: painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specification MORTH chapter 8	Rmt	8.00	63.60	Rupees sixty three and paise sixty only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Yelahanka Division
BBMP, Bangalore - 64